

Schedule of Quantity for: "Repairing / modification of drain at Turamdih Township"

N. I. T No.: TMD/MIN – 706

[P R I C E P A R T]

Schedule of Quantity for: **"Repairing / modification of drain at Turamdih Township."**

N. I. T No. TMD/MIN - 706

| Item No. | Description of item | Qty | Unit | Rate Rs. P | Rate in words | Amount Rs. P |
|----------|---|---------------|------------|---------------|---------------|-----------------|
| 1 | Earth work in excavation in foundation trenches, pits or drains not exceeding 1.5 Mtr in depth, 2 Mtr in width as well as 10 Sq.m on plan including clearing of bushes and shrubs from ground level including trimming dressing of sides and ramming of bottoms, lift upto 1.5 Mtr including dewatering getting out the excavated soil and disposal of surplus excavated soil within a lead of 100 m including cost of all materials, labour, tools and tackles etc. as per drawings, specifications and directions of Engineer-in-charge. a) Ordinary/ dense soil mixed with gravels / rock fragments / loose waste | 260.00 | CUM | | | |
| 2 | Earth work in back filling with available earth including watering and compaction at all elevations around foundations, walls, wells, tunnels, pits, culverts trenches, road approaches and in plinth filling and area filling as per specifications and drawings and as directed by the engineer-in-charge with selected spoils within a lead of 100 Mtr. including cost of all materials, labour, tools and tackles etc. | 48.00 | CUM | | | |

N. I. T No. TMD/MIN - 706

| Item No. | Description of item | Qty | Unit | Rate Rs. P | Rate in words | Amount Rs. P |
|----------|--|--------------|------------|---------------|---------------|-----------------|
| 3 | Supply, mix place in position compact & cure cement concrete 1:3:6 (1 Cement: 3 coarse sand: 6) graded stone aggregate 20mm nominal size below foundations, walls, wells, pits, trenches etc. as per specifications, drawings and directions of the Engineer -in-charge including cost of all materials, labour, tools and tackles etc. including cost of cement, centring and shuttering. | 20.00 | CUM | | | |
| 4 | Random rubble masonry with hard stone in foundation and plinth including levelling up with cement concrete 1 : 6 : 12 (1 cement : 6 coarse sand : 12 graded stone aggregate 20 mm nominal size) at plinth level with cement mortar 1 : 6 (1 cement : 6 coarse sand) | 96.00 | CUM | | | |
| 5 | Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20mm nominal size | 8.00 | CUM | | | |

N. I. T No. TMD/MIN - 706

| Item No. | Description of item | Qty | Unit | Rate Rs. P | Rate in words | Amount Rs. P |
|----------|---|--------|------|---------------|---------------|-----------------|
| 6 | Providing and laying 600 mm dia RCC pipe non-pressure NP2 class (light duty) RCC pipes with collars jointed with stiff mixture of cement mortar in the proportion of 1: 2 (1 Cement : 2 fine sand) including testing of joints etc complete as per the direction of EIC. | 20.00 | RM | | | |
| 7 | Supply and laying in position brick work with designate 75 bricks (compressive strength not less than 75 Kg/Sq.cm) in foundation, trench and upto plinth in cement-coarse sand mortar (1:6) including mixing mortar, laying bricks, raking joints, curing etc. complete with all materials and labour but including cost of cement as per drawings and specifications. | 3.00 | CUM | | | |
| 8 | 15 mm thick (minimum) plastering with 1:6 (1 cement:6 coarse sand) to walls, channels in roof and other structures at various elevations including demolishing old plaster (if require), mixing, laying finishing, curing and necessary scaffolding work complete as per drawings, specifications and instructions of the Engineer with all materials and labour but including cost cement. | 100.00 | Sqm | | | |
| | Total | | | | | |
| | Rebate if any in words (_____) | | | | % | |
| | Grand Total | | | | | |

(Total in words)

NOTE:

| |
|---|
| 1. All items rates must be written in figures and words without which tenders are liable to be rejected. |
| 2. All the pages of tender document must be duly signed by tenderer along with their seal. |
| 3. Overall rebate, if any must be quoted in the above column only and written elsewhere shall not be considered. |
| 4. Conditional tender submitted by the tenderer will be summarily rejected without any prejudice, hence tenderer are advice to quote their rates as per N. I. T conditions. |
| 5. The Quoted rate should be inclusive of all taxes and duties including Service Tax |

Signature with Seal